

50% Construction Document Estimate

Project: McKinney RHHL Renovation
Date: March 28, 2025



BID PACKAGE	DESCRIPTION	Subcontractor/ Supplier	Sitework	Library Renovation	GBSF 33,670 \$/SF	GBSF 33,670 \$/SF	GBSF 33,670 \$/SF	%
TOTAL								
01A	General Conditions	CROSSLAND	\$ 15,829	\$ 142,458	\$ 4.23	\$ 158,287	\$ 4.70	0.90%
02A	Selective Demolition		\$ 150,000	\$ 165,566	\$ 4.92	\$ 315,566	\$ 9.37	1.79%
31A	Earthwork		\$ 200,000	\$ 50,000	\$ 1.49	\$ 250,000	\$ 7.43	1.42%
32A	Site Paving		\$ 176,500	\$ -	\$ -	\$ 176,500	\$ 5.24	1.00%
32B	Landscaping & Irrigation		\$ 150,000	\$ -	\$ -	\$ 150,000	\$ 4.46	0.85%
32C	Fencing		\$ 75,000	\$ -	\$ -	\$ 75,000	\$ 2.23	0.43%
32D	Retaining Walls		\$ 50,000	\$ -	\$ -	\$ 50,000	\$ 1.49	0.28%
33A	Site Utilities		\$ 100,000	\$ -	\$ -	\$ 100,000	\$ 2.97	0.57%
03A	Cast-in-Place Concrete		\$ -	\$ 205,157	\$ 6.09	\$ 205,157	\$ 6.09	1.17%
03B	Polished /Sealed Concrete		\$ -	\$ 2,500	\$ 0.07	\$ 2,500	\$ 0.07	0.01%
03P	Unit Pavers		\$ 73,500	\$ -	\$ -	\$ 73,500	\$ 2.18	0.42%
04A	Masonry		\$ -	\$ 278,430	\$ 8.27	\$ 278,430	\$ 8.27	1.58%
05A	Structural & Miscellaneous Steel		\$ -	\$ 427,150	\$ 12.69	\$ 427,150	\$ 12.69	2.43%
05B	Railings			\$ 191,250	\$ 5.68	\$ 191,250	\$ 5.68	1.09%
06A	Woods and Plastics		\$ -	\$ 199,843	\$ 5.94	\$ 199,843	\$ 5.94	1.14%
07A	Roofing		\$ -	\$ 253,863	\$ 7.54	\$ 253,863	\$ 7.54	1.44%
07B	Waterproofing		\$ 2,328	\$ 49,919	\$ 1.48	\$ 52,247	\$ 1.55	0.30%
07C	Fireproofing		\$ -	\$ -	\$ -	\$ -	\$ -	0.00%
07D	Metal Panels		\$ -	\$ 558,066	\$ 16.57	\$ 558,066	\$ 16.57	3.17%
08A	Doors & Hardware		\$ -	\$ 264,850	\$ 7.87	\$ 264,850	\$ 7.87	1.50%
08B	Glass & Glazing		\$ -	\$ 400,750	\$ 11.90	\$ 400,750	\$ 11.90	2.28%
09A	Drywall & Acoustical		\$ -	\$ 994,513	\$ 29.54	\$ 994,513	\$ 29.54	5.65%
09B	Flooring		\$ -	\$ 350,549	\$ 10.41	\$ 350,549	\$ 10.41	1.99%
09C	Tile		\$ -	\$ 107,636	\$ 3.20	\$ 107,636	\$ 3.20	0.00%
09D	Painting		\$ -	\$ 176,376	\$ 5.24	\$ 176,376	\$ 5.24	1.00%
09T	Terrazzo		\$ -	\$ 234,500	\$ 6.96	\$ 234,500	\$ 6.96	1.33%
10A	Miscellaneous Specialties		\$ -	\$ 78,600	\$ 2.33	\$ 78,600	\$ 2.33	0.45%
10B	Signage	Code Minimum	\$ 45,500	\$ 21,000	\$ 0.62	\$ 66,500	\$ 1.98	0.38%
11A	Equipment		\$ -	\$ 3,000	\$ 0.09	\$ 3,000	\$ 0.09	0.02%
12A	Furnishings		\$ -	\$ 1,657,985	\$ 49.24	\$ 1,657,985	\$ 49.24	9.42%
13A	Planetarium		\$ -	\$ 986,673	\$ 29.30	\$ 986,673	\$ 29.30	5.60%
14A	Conveying Equipment		\$ -	\$ 238,500	\$ 7.08	\$ 238,500	\$ 7.08	1.35%
21A	Fire Protection		\$ -	\$ 206,033	\$ 6.12	\$ 206,033	\$ 6.12	1.17%
22A	Plumbing		\$ -	\$ 378,320	\$ 11.24	\$ 378,320	\$ 11.24	2.15%
23A	HVAC		\$ -	\$ 1,497,349	\$ 44.47	\$ 1,497,349	\$ 44.47	8.51%
26A	Electrical		\$ 50,000	\$ 1,922,520	\$ 57.10	\$ 1,972,520	\$ 58.58	11.21%
27A	Communications	Excluded	\$ -	\$ 297,005	\$ 8.82	\$ 297,005	\$ 8.82	1.69%
27B	Audio/Visual		\$ -	\$ 1,469,175	\$ 43.63	\$ 1,469,175	\$ 43.63	8.35%
28A	Fire Alarm		\$ -	\$ 45,455	\$ 1.35	\$ 45,455	\$ 1.35	0.26%
28B	Security		\$ -	\$ 131,255	\$ 3.90	\$ 131,255	\$ 3.90	0.75%
28C	Access Controls		\$ -	\$ 59,500	\$ 1.77	\$ 59,500	\$ 1.77	0.34%
28D	Emergency Radio Communication System		\$ -	\$ -	\$ -	\$ -	\$ -	0.00%
SUBTOTAL DIRECT COST OF WORK		Subtotal Direct Cost	\$ 1,088,656	\$ 14,045,743	\$ 417.16	\$ 15,134,399	\$ 449.49	85.97%
	Design/Market Risk Contingency		\$ 25,654	\$ 326,423	\$ 9.69	\$ 352,077	\$ 10.46	2.00%
	Construction Contingency	CROSSLAND	\$ 25,654	\$ 326,423	\$ 9.69	\$ 352,077	\$ 10.46	2.00%
	Owner's Contingency		\$ 25,654	\$ 326,423	\$ 9.69	\$ 352,077	\$ 10.46	2.00%
	Building Permit & Plan Review Fees	CROSSLAND	\$ -	\$ -	\$ -		\$ -	0.00%
	Builders Risk	CROSSLAND	\$ 1,924	\$ 24,482	\$ 0.73	\$ 26,406	\$ 0.78	0.15%
	General Commercial Liability	CROSSLAND	\$ 4,489	\$ 57,124	\$ 1.70	\$ 61,613	\$ 1.83	0.35%
	Payment and Performance Bond		\$ 6,413	\$ 81,606	\$ 2.42	\$ 88,019	\$ 2.61	0.50%
	Subcontractor Default Insurance		\$ 17,316	\$ 220,336	\$ 6.54	\$ 237,652	\$ 7.06	1.35%
	CMAR - Office & Field Staff	CROSSLAND	\$ 40,240	\$ 362,162	\$ 10.76	\$ 402,403	\$ 11.95	2.29%
	Preconstruction Phase Fee	CROSSLAND	\$ 5,000	\$ 20,000	\$ 0.59	\$ 25,000	\$ 0.74	0.14%
	Construction Phase Fee	CROSSLAND	\$ 41,687	\$ 530,438	\$ 15.75	\$ 572,125	\$ 16.99	3.25%
TOTAL ESTIMATED COST			\$ 1,282,688	\$ 16,321,160	\$ 484.74	\$ 17,603,848	\$ 522.83 /SF	

DD Estimate 3/4/2025	Delta
\$ 158,287	\$ -
\$ 354,909	\$ (39,344)
\$ 356,219	\$ (106,219)
\$ 342,025	\$ (165,525)
\$ 175,000	\$ (25,000)
\$ 75,000	\$ -
\$ 67,080	\$ (17,080)
\$ 100,000	\$ -
\$ 233,522	\$ (28,365)
\$ 875	\$ 1,625
\$ 127,500	\$ (54,000)
\$ 196,250	\$ 82,180
\$ 460,700	\$ (33,550)
\$ 170,000	\$ 21,250
\$ 194,918	\$ 4,925
\$ 312,075	\$ (58,212)
\$ 82,028	\$ (29,781)
\$ 25,000	\$ (25,000)
\$ 350,730	\$ 207,336
\$ 272,150	\$ (7,300)
\$ 584,625	\$ (183,875)
\$ 564,420	\$ 430,093
\$ 282,753	\$ 67,797
\$ 104,517	\$ 3,119
\$ 315,336	\$ (138,961)
\$ 224,000	\$ 10,500
\$ 68,050	\$ 10,550
\$ 31,685	\$ 34,816
\$ 3,000	\$ -
\$ 1,737,340	\$ (79,355)
\$ 1,016,450	\$ (29,777)
\$ 220,000	\$ 18,500
\$ 149,378	\$ 56,655
\$ 297,078	\$ 81,243
\$ 813,293	\$ 684,058
\$ 1,621,974	\$ 350,546
\$ 227,273	\$ 69,733
\$ 642,675	\$ 826,500
\$ 45,455	\$ -
\$ 143,040	\$ (11,785)
\$ 75,000	\$ (15,500)
\$ -	\$ -
\$ 13,221,606	\$ 1,912,794
\$ 468,501	\$ (116,424)
\$ 312,334	\$ 39,743
\$ 312,334	\$ 39,743
	\$ -
\$ 23,425	\$ 2,981
\$ 54,658	\$ 6,955
\$ 78,084	\$ 9,936
\$ 210,826	\$ 26,826
\$ 402,403	\$ -
\$ 25,000	\$ -
\$ 507,543	\$ 64,582
\$ 15,616,714	\$ 1,987,134

50% Construction Documents Estimate

Project: McKinney RHHL Renovation

Date: March 28, 2025



Estimate Detail				Unit	Unit Cost	Amount
Area	Item					
Site	02A EXISTING CONDITIONS					
Site	1	Tree Removal	80	EA	\$ 500.00	\$ 40,000
Site	2	Large Tree Protection	6	EA	\$ 1,750.00	\$ 10,500
Site	3	Demo Existing Retaining & Planter Walls	291	LF	\$ 150.00	\$ 43,700
Site	4	Northwest Corner - Concrete Demo for New Door	1,500	SF	\$ 8.00	\$ 12,000
Site	5	Southwest Corner - Concrete Demo - Washout Area	2,350	SF	\$ 8.00	\$ 18,800
Site	6	Protection of Adjacent Surfaces	1	LS	\$ 25,000.00	\$ 25,000
02A EXISTING CONDITIONS						150,000
31A EARTHWORK						
Site	7	Install/Maintain/Remove SWPPP BMP's (ie. silt fence, inlet protection, etc...)	829	LF	3.00	2,486
Site	8	Temporary Pathways, Structures, Road Plates for Public Safety	1	LS	20,000.00	20,000
Site	9	Clearing & Grubbing	15,200	SF	2.50	38,000
Site	10	Strip & Stockpile Topsoil	563	CY	3.50	1,970
Site	11	Rough Grading - assumes 5' across South of Building	2,815	CY	8.50	23,926
Site	12	Import / Export	2,111	CY	14.00	29,556
Site	13	Fine Grading for Landscaping & Sidewalks	13,850	SF	1.00	13,850
Site	14	Backfill Curbs/Islands	352	LF	18.50	6,512
Site	15	Respread Topsoil	11,700	CY	2.50	29,250
Site	16	Northwest Corner - Grading Rework for New Door	1,500	SF	6.30	9,450
Site	17	Traffic & Dust Control	1	LS	25,000.00	25,000
31A EARTHWORK						200,000
32A SITE PAVING						
Site	18	Heavy Duty Paving - Dumpster - 8" Thick 3600 PSI		SF	8.50	-
Site	19	Medium Duty Paving - Fire Lane & Truck Court - 6" Thick 3600 PSI		SF	8.00	-
Site	20	Light Duty Paving - Parking - 5" thick 3600 PSI - Front Entrances	1,500	SF	15.00	22,500
Site	21	Concrete Sidewalk, 4" 3600 PSI - Bookdrop & New Entrances	1,650	SF	9.50	15,675
Site	22	Concrete Sidewalk, 4" 3600 PSI - Courtyard	3,500	SF	8.50	29,750
Site	23	Concrete Paver Base - Courtyard	3,500	SF	7.50	26,250
Site	24	Unit Pavers	3,500	SF	21.00	73,500
Site	25	Concrete Stair Rework	1	LS	50,000.00	50,000
Site	26	Extend Existing Retaining Wall	192	VSF	135.00	25,920
Site	27	Barrier Free Ramps		EA	750.00	-
Site	28	Transform Pad	-	EA	5,000.00	-
Site	29	Light Pole Bases		EA	3,000.00	-
Site	30	Pipe Bollards		EA	500.00	-
Site	31	Pavement Markings	3,905	SF	1.00	3,905
Site	32	ADA Parking Signs	5	EA	500.00	2,500
Site	33	Concrete Wheel Stops		EA	120.00	-
32A SITE PAVING						250,000
32B RETAINING WALLS						
Site	34	Segmented Block Retaining Wall - 3' Height = 2 EA per Side	1,032	SF	48.45	50,000
32B RETAINING WALLS						50,000
32C LANDSCAPING & IRRIGATION						
Site	35	Landscaping, - ALLOWANCE	1.00	ALLOW	100,000.00	100,000
Site	36	Irrigation System Adjustments for New Landscape	13,850.00	SF	3.61	50,000
Site	37	Landscaping Maintenance		MO	350.00	-
32C LANDSCAPING & IRRIGATION						150,000
32D FENCING						
Site	38	Courtyard Ornamental Fence	360	LF	175.00	63,000
Site	39	Courtyard Ornamental Gate Double Man Gate	1	EA	12,000.00	12,000
32D FENCING						75,000

50% Construction Documents Estimate

Project: McKinney RHHL Renovation

Date: March 28, 2025



Estimate Detail						
Area	Item			Unit	Unit Cost	Amount
33A SITE UTILITIES						
Site	40	Storm - Roof Drain Adjustments - North Elevation Repairs	1	LS	75,000.00	75,000
Site	41	Storm - Courtyard Drainage	1	LS	25,000.00	25,000
Site	42	Haul Spoils		CY	25.00	-
33A SITE UTILITIES						100,000
04A MASONRY						
Site	43	CMU for Dumpster Enclosure		SF	28.00	-
04A MASONRY						-
05A STRUCTURAL & MISCELLANEOUS STEEL - FABRICATION						
Site	44	Dumpster Gate		EA	7,500.00	-
05A STRUCTURAL STEEL - FABRICATION						-
07B WATERPROOFING						
Site	45	Joint Sealants - Site Paving and Sidewalks	6,650	SF	0.35	2,328
07B WATERPROOFING						2,328
09D PAINTING						
Site	46	Painting, Exterior		LS	\$ 15,000.00	\$ -
09D PAINTING \$						-
10A SPECIALTIES						
Site	46	Flag Poles		EA	3,000.00	-
10A SPECIALTIES						-
10B SIGNAGE						
Site	47	"LIBRARY" - 46" Tall Illuminated Letters	7	EA	3,500.00	24,500
Site	48	"ROY & HELEN HALL MEMORIAL" - 12" Tall Illuminated Letters	21	EA	1,000.00	21,000
10B SIGNAGE						45,500
10C COVERED WALKWAYS						
Site	49	Pre-Manufactured Covered Walkways		EA	55.00	-
10C COVERED WALKWAYS						-
26A ELECTRICAL						
Site	50	Electrical, Primary Conduits, Empty, Direct Buried		LF	\$ 100.00	-
Site	51	Electrical, Secondary Conduits and Wire, Direct Buried		LF	\$ 250.00	-
Site	52	Electrical, Site Lighting & Bollards not Shown	1.00	ALLOW	\$ 50,000.00	50,000
26A ELECTRICAL						50,000
27A COMMUNICATIONS						
Site	53	Telecomm Service, (3) Empty 4" PVC Conduits, Direct Buried		LF	50.00	-
27A COMMUNICATIONS						-

50% Construction Documents Estimate

Project: McKinney RHHL Renovation
Date: March 28, 2025



Estimate Detail						
Area	Item	Description		Unit	Unit Cost	Amount
02A EXISTING CONDITIONS						
Building	54	First Floor Demo Existing Finishes, Walls	17,933	SF	\$ 2.25	\$ 40,349
Building	55	Second Floor Demo Existing Finishes, Walls	15,338	SF	\$ 2.25	\$ 34,511
Building	56	Slab Cut Allowance - 20% of floor square footage	6,654	SF	\$ 5.00	\$ 33,271
Building	57	Demo Existing Sidewalk under Porch	1,487	SF	\$ 5.00	\$ 7,435
Building	58	Temporary Partitions and Dust Control	33,670	SF	\$ 1.49	\$ 50,000
02A EXISTING CONDITIONS						\$ 165,566
31A EARTHWORK						
Building	59	Elevator Pit Excavation	1	LS	\$ 25,000.00	\$ 25,000
Building	60	Haul Road and Rework of Crane path	1	LS	\$ 25,000.00	\$ 25,000
Building	61	New 5" Slab on Grade - Over Exc & 4' Select Fill	-	CY	\$ 64.00	\$ -
Building	62	Fine Grading New Slab on Grade	-	SF	\$ -	\$ -
31A EARTHWORK						\$ 50,000
03A CAST-IN-PLACE CONCRETE						
Building	63	Replace Slab on Grade - Plumbing Change	6,654	SF	\$ 7.50	\$ 49,907
Building	64	New Piers at Elevator and New Porches - 18' Deep + 5' Penetration	4	EA	\$ 2,415.00	\$ 9,660
Building	65	Grade Beam - 2.17'W x 2.33'D	192	LF	\$ 250.00	\$ 48,000
Building	66	Grade Beam - 1.17'W x 2.17'D	64	LF	\$ 185.00	\$ 11,840
Building	67	Elevator Pit Walls - 1.17'W x 5'D	54	LF	\$ 350.00	\$ 18,900
Building	68	Elevator Pit Slab - 10" Thick	255	SF	\$ 55.00	\$ 14,025
Building	69	Fill in existing Elevator Pit	55	SF	\$ 15.00	\$ 825
Building	70	Connect to Existing Slab	196	LF	\$ 85.00	\$ 16,660
Building	71	New 5" Slab on Grade - New Porch	1,920	SF	\$ 12.50	\$ 24,000
Building	72	Slab on Metal Decking	630	SF	\$ 18.00	\$ 11,340
03A CAST-IN-PLACE CONCRETE						\$ 205,157
03B POLISHED CONCRETE						
Building	72	SCN1 Sealed Concrete	250	SF	\$ 8.50	\$ 2,125
Building	73	Joint Sealants at Polished Flooring	250	SF	\$ 1.50	\$ 375
03B POLISHED CONCRETE						\$ 2,500
04A MASONRY						
Building	74	Point and Patch Existing Masonry	28,665	SF	\$ 2.62	\$ 75,000
Building	75	Portland Cement Plaster Behind Perforated Metal Screen	4,381	SF	\$ 30.00	\$ 131,430
Building	76	Brick Infill per Elevations	1,800	SF	\$ 40.00	\$ 72,000
04A MASONRY						\$ 278,430
05A STRUCTURAL & MISCELLANEOUS STEEL - FABRICATION						
Building	77	Structural Steel Adjustments to Existing Structure - New Porches	1,750	SF	\$ 50.00	\$ 87,500
Building	78	Additional Structure for Planetarium Popup	20	Tons	\$ 5,500.00	\$ 110,000
Building	79	Miscellaneous Steel (ie. Embeds, Lintels, Anchor Bolts, etc...)	1	LS	\$ 15,000.00	\$ 15,000
Building	80	Structural Adjustments for new second Floor Balcony	630	SF	\$ 55.00	\$ 34,650
Building	81	New Elevator Shaft Columns	1	LS	\$ 25,000.00	\$ 25,000
Building	82	Relocation of Braced Frames	2	EA	\$ 7,500.00	\$ 15,000
Building	83	Shoring of Existing Structure	1,750	SF	\$ 57.14	\$ 100,000
Building	84	Erection - Structural Steel	20	TONS	\$ 2,000.00	\$ 40,000
05A STRUCTURAL STEEL - FABRICATION						\$ 427,150
05B Railings						
Building	85	Stair Handrail Upgrades - Viva Railings	175	LF	\$ 750.00	\$ 131,250
Building	86	Bridge Handrail Upgrade - Viva Railings	80	LF	\$ 750.00	\$ 60,000
05B Railings						\$ 191,250

50% Construction Documents Estimate

Project: McKinney RHHL Renovation
Date: March 28, 2025



Estimate Detail						
Area	Item	Description		Unit	Unit Cost	Amount
06A WOODS AND PLASTICS						
Building	87	Rough Carpentry	33,670	SF	\$ 0.25	\$ 8,418
Building	88	100 Lobby - PL-01 Wall Panels - 2&4/A4.11	920	SF	\$ 65.00	\$ 59,800
Building	89	120 Multipurpose Plam Upper Cabinets- 1/A4.14	15	LF	\$ 350.00	\$ 5,250
Building	90	120 Multipurpose Plam Lower Cabinets with Soild Surface CT - 1/A4.14	15	LF	\$ 550.00	\$ 8,250
Building	91	130 Youth - Plam & Solid Surface Radius Wall Feature - 2&4 /A4.14	1	ALLOW	\$ 25,000.00	\$ 25,000
Building	92	151 Teen Room - Plam Bench with LVT-01 - 5 & 8/A4.12	35	LF	\$ 750.00	\$ 26,250
Building	93	162 Staff Lounge - Plam Upper Cabinets - 8/A4.13	8	LF	\$ 350.00	\$ 2,800
Building	94	162 Staff Lounge - Plam Lower Cabinets with Solid Surface CT - 8/A4.13	10	LF	\$ 550.00	\$ 5,500
Building	95	Trim Paint Grade Chair Rail	75	LF	\$ 25.00	\$ 1,875
Building	96	Paint Grade Base	300	LF	\$ 25.00	\$ 7,500
Building	97	121 Storage - Plam Upper Cabinets	16	LF	\$ 250.00	\$ 4,000
Building	98	121 Storage - Plam Lower Cabinets with Soild Surface CT	16	LF	\$ 350.00	\$ 5,600
Building	99	260 Adult Collection - PLAM Banquette w/ Upholstery - 2/A4.16 & 7/A4.15	16	LF	\$ 750.00	\$ 12,000
Building	100	260 Adult Collection - Soild Surface Countertop - 2/A4.16 & 7/A4.15	16	SF	\$ 100.00	\$ 1,600
Building	101	261 - Local History Reaseach Room - Clear Sealed Bitch Full Height Bookshelves	26	LF	\$ 1,000.00	\$ 26,000
06A WOODS AND PLASTICS						\$ 199,843
07A ROOFING						
Building	102	Standing Seam Roof Demo & Rework	3,650	SF	\$ 28.00	\$ 102,200
Building	103	Planetarium & Chimey Standing Seam Roofing - R25 with 1/2" Coverboard	1,275	SF	\$ 28.00	\$ 35,700
Building	104	Elevator Shaft Flat Roof - R-25, 60Mil TPO Roof - 1/2" Coverboard, Fully Adhered	348	SF	\$ 45.00	\$ 15,638
Building	105	Standing Seam Roofing - Doghouse	150	SF	\$ 28.00	\$ 4,200
Building	106	Colorguard Snow Retention System	845	LF	\$ 25.00	\$ 21,125
Building	107	Cleaning and Repairing Existing Roofing	24,489	SF	\$ 3.06	\$ 75,000
07A ROOFING						\$ 253,863
07B WATERPROOFING						
Building	108	Fluid Applied Air Barrier	6,181	SF	\$ 4.25	\$ 26,269
Building	109	Elevator Pit Dampproofing	270	SF	\$ 45.00	\$ 12,150
Building	110	Flexible Flashing	250	LF	\$ 28.00	\$ 7,000
Building	111	Joint Sealants - Slab-on-Grade		SF	\$ 0.25	\$ -
Building	112	Joint Sealants - Masonry	1,800	SF	\$ 2.50	\$ 4,500
Building	113	Joint Sealants - Windows/Doors/Dissimilar Materials		LF	\$ 3.00	\$ -
07B WATERPROOFING						\$ 49,919
07C SPRAY FIREPROOFING						
Building	114	Spray Applied Fireproofing ALLOWANCE	-	LS	25,000.00	-
07C SPRAY FIREPROOFING						-
07D METAL PANELS						
Building	115	Metal Wall Panels - Elevator Shaft	1,350	SF	\$ 109.28	\$ 147,528
Building	116	Metal Wall Panels - Planetarium	825	SF	\$ 109.28	\$ 90,156
Building	117	Perforated Metal Panel - Exterior Infill	2,206	SF	\$ 109.28	\$ 241,072
Building	118	Perforated Metal Screen Fence for Signage	680	SF	\$ 109.28	\$ 74,310
Building	119	Perforated Metal Screen Gate	1	EA	\$ 5,000.00	\$ 5,000
Building	120	Rigid Insulation	-	SF	\$ 3.50	\$ -
Building	121	Metal Panel Soffit		SF	\$ 35.00	\$ -
07D METAL PANELS						\$ 558,066
08A DOORS AND HARDWARE						
Building	122	Hollow Metal Door Frames 3070	31	EA	\$ 750.00	\$ 23,250
Building	123	Hollow Metal Doors Frame 6070	4	EA	\$ 950.00	\$ 3,800
Building	124	Hollow Metal Door 3070	2	LEAF	\$ 850.00	\$ 1,700
Building	125	Wood Doors 3070 - Plain Sliced Red Oak Veneer	48	LEAF	\$ 1,200.00	\$ 57,600
Building	126	Hardware Allowance - No Specifications	56	EA	\$ 1,500.00	\$ 84,000
Building	127	Doors & Hardware Installation	50	EA	\$ 450.00	\$ 22,500
Building	128	STC RATING on DOORS	48	EA	\$ 1,500.00	\$ 72,000
08A DOORS AND HARDWARE						\$ 264,850

50% Construction Documents Estimate

Project: McKinney RHHL Renovation
Date: March 28, 2025



Estimate Detail						
Area	Item	Description		Unit	Unit Cost	Amount
08B GLASS & GLAZING						
Building	129	Storefront Openings - First Floor Infill	1,210	SF	\$ 75.00	\$ 90,750
Building	130	Storefront Entrances 3070 - 102A, 130A, 164A, 164B	4	EA	\$ 5,500.00	\$ 22,000
Building	131	Storefront Entrances 6070 - 120A,151A,160A, 261A	4	PAIR	\$ 8,000.00	\$ 32,000
Building	132	Door Type AL - Wood Door with Glass Insert - 152A,161A,162A,163A,165A,166A,167A,168A,220A,232A,233A,234A,235A,263A,264A,265A,266A	17	EA	\$ 350.00	\$ 5,950
Building	133	C1 - Curtian Wall - Doghouse - 2 EA	140	SF	\$ 95.00	\$ 13,300
Building	134	Replace Bi-Parting Slider Doors at Vesitbules	4	EA	\$ 25,000.00	\$ 100,000
Building	135	Interior Storefront - 10' Tall	2,150	SF	\$ 45.00	\$ 96,750
Building	136	Storefront Door Hardware	8	EA	\$ 5,000.00	\$ 40,000

08B GLASS & GLAZING \$ 400,750

09A DRYWALL & ACOUSTICAL						
Building	138	Exterior Framing	6,781	SF	\$ 17.50	\$ 118,668
Building	139	Exterior Sheathing	6,781	SF	\$ 4.50	\$ 30,515
Building	140	Insulation, Batt added STC Ratings	42,333	SF	\$ 2.50	\$ 105,833
Building	141	Single 1 sided Furred Drywall	19,984	SF	\$ 5.50	\$ 109,912
Building	142	2 sided Interior Drywall Partitions - Full Height	15,568	SF	\$ 12.50	\$ 194,600
Building	143	Furdowns	2,163	SF	\$ 15.00	\$ 32,445
Building	144	HM Door Frames, Installation	35	EA	\$ 150.00	\$ 5,250
Building	145	Aluminum Framing for Offices	309	LF	\$ 105.00	\$ 32,445
Building	146	Gypsum Ceilings	10,722	SF	\$ 5.50	\$ 58,971
Building	147	ACT1 Acoustic Ceiling Tile 24"x24"	10,394	SF	\$ 12.50	\$ 129,925
Building	148	Planetarium - Domed Framing	1,275	SF	\$ 65.00	\$ 82,875
Building	149	Acoustical Compact Spring System at Planetarium Ceiling	1,275	SF	\$ 38.00	\$ 48,450
Building	150	STC Rating in Planetarium Walls	1,275	SF	\$ 35.00	\$ 44,625

09A DRYWALL & ACOUSTICAL \$ 994,513

09B FLOORING						
Building	151	CPT-01 Carpet Tile - Kinetex 1850 24"x24"	345	SY	\$ 48.98	\$ 16,901
Building	152	CPT-02A Carpet Tile - Kinetex 1850 24"x24" - Assumed 25%	180	SY	\$ 45.98	\$ 8,288
Building	153	CPT-02B Carpet Tile - Kinetex 1850 24"x24" - Assumed 25%	180	SY	\$ 45.98	\$ 8,288
Building	154	CPT-02C Carpet Tile - Kinetex 1850 24"x24" - Assumed 25%	180	SY	\$ 45.98	\$ 8,288
Building	155	CPT-02D Carpet Tile - Kinetex 1850 24"x24" - Assumed 25%	180	SY	\$ 45.98	\$ 8,288
Building	156	CPT-03 Carpet Tile - Kinetex 1843 24"x24"	67	SY	\$ 48.89	\$ 3,273
Building	157	LVT-01 Luxury Vinyl Tile - Bolon Stidio - Artisan - WING and Bigger Shapes	1,045	SF	\$ 22.25	\$ 23,251
Building	158	LVT-02 Luxury Vinyl Tile -Milliken - Lumenology	6,180	SF	\$ 7.75	\$ 47,895
Building	159	RF-01 - Rubber Flooring - Nora - Norament - Arago 39.53"x19.76"	1,947	SF	\$ 15.93	\$ 31,011
Building	160	RF-02 - Rubber Flooring - Nora - Norament - Arago 39.53"x19.76" - 5172 Stamina	1,288	SF	\$ 15.93	\$ 20,510
Building	161	RF-03 - Rubber Flooring - Nora - Norament - Grano 39.53"x39.53" - NOT AVAILABLE IN SPECIFIED SIZE	2,961	SF	\$ 15.93	\$ 47,173
Building	162	RF-04 - Rubber Flooring - Nora - Norament - Grano ED 39.53"x39.53"	335	SF	\$ 20.64	\$ 6,909
Building	163	RF-05A - Rubber Flooring - Atmosphere Blueprint - 25% Mix	1,200	SF	\$ 15.50	\$ 18,600
Building	164	RF-05B - Rubber Flooring - Atmosphere Blueprint - 25% Mix	1,200	SF	\$ 15.50	\$ 18,600
Building	165	RF-06A - Rubber Flooring - Atmosphere Blueprint - 25% Mix	1,200	SF	\$ 15.50	\$ 18,600
Building	166	RF-06B - Rubber Flooring - Atmosphere Blueprint - 25% Mix	1,200	SF	\$ 15.50	\$ 18,600
Building	167	VCT1 Vinyl Composition Tile	-	SF	\$ 3.50	\$ -
Building	168	Lobby Wood Flooring	225	SF	\$ 55.00	\$ 12,375
Building	169	Transition Allowance	1	ALLOW	\$ 10,000.00	\$ 10,000
Building	170	RB-1 Rubber Base	4,280	LF	\$ 2.50	\$ 10,700
Building	171	WM-01 - Aluminum Walk off Matt	2	EA	\$ 6,500.00	\$ 13,000

09B FLOORING \$ 350,549

09C TILE						
Building	171	CT-01- Ceramic Tile - Restroom Floors - Thorntree Ashima 24x24"	890	SF	\$ 15.80	\$ 14,062
Building	172	WT-01 - Ceramic Wall Tile - Vanity Walls- Thorentree - Oxid 3x12 Emerald	650	SF	\$ 20.33	\$ 13,215
Building	173	WT-02 - Ceramic Wall Tile - Thorentree - Oxid 3x12 Silver - Assumed 50%	1,890	SF	\$ 15.72	\$ 29,711
Building	174	WT-01 - Ceramic Wall Tile - Thorentree - Oxid 3x12 Titanium - Assumed 50%	1,890	SF	\$ 15.72	\$ 29,711
Building	175	Ceramic Wall Tile at Water Fountain - \$6/SF Material Allowance	30	SF	\$ 25.25	\$ 758
Building	176	Ceramic Wall Tile at Staff Lounge & Multipurpose Backsplash - \$15/SF Material Allowance	50	SF	\$ 35.05	\$ 1,753
Building	177	Schluters Transitions & Trim	1	LS	\$ 5,500.00	\$ 5,500
Building	178	Epoxy Grout at Restroom Wall & Water Fountain Wall Tile Only	3,925	SF	\$ 2.50	\$ 9,813
Building	179	Waterproofing/Crack Isolation Membrane	890	SF	\$ 1.50	\$ 1,335
Building	180	Floor Prep	890	SF	\$ 2.00	\$ 1,780

09C TILE \$ 107,636

50% Construction Documents Estimate

Project: McKinney RHHL Renovation
Date: March 28, 2025



Estimate Detail						
Area	Item	Description		Unit	Unit Cost	Amount
09D PAINTING						
Building	181	PT1 - PT6 Painting, Interior Walls	35,552	SF	\$ 1.50	\$ 53,328
Building	182	Paint Gypsum Ceilings	11,669	SF	\$ 2.50	\$ 29,173
Building	183	Elevator Elevation Wall Covering	550	SF	\$ 35.00	\$ 19,250
Building	184	Painting Exposed Ceilings	9,850	SF	\$ 2.50	\$ 24,625
Building	185	RP-01 - Planetarium /Stair wall covering	-	SF	\$ 50.00	\$ -
Building	186	Undefined - Vinyl Wall Covering	1,000	SF	\$ 50.00	\$ 50,000
09D PAINTING						\$ 176,376
09T TERRAZZO						
Building	187	Terrazzo Lobby	5,625	SF	\$ 28.00	\$ 157,500
Building	188	Terrazzo Second Floor Bridge	1,250	SF	\$ 28.00	\$ 35,000
Building	189	Terrazzo Stair Treads	42	EA	\$ 1,000.00	\$ 42,000
09T TERRAZZO						\$ 234,500
10A MISCELLANEOUS SPECIALTIES						
Building	190	Grab Bar, Stainless Steel 36"	11	EA	\$ 250.00	\$ 2,750
Building	191	Grab Bar, Stainless Steel 42"	11	EA	\$ 350.00	\$ 3,850
Building	192	Mirror, Vanity, Stainless Steel Frame	-	EA	\$ 500.00	\$ -
Building	193	Toilet Paper Dispenser	11	EA	\$ 550.00	\$ 6,050
Building	194	Sanitary Napkin Disposal	11	EA	\$ 350.00	\$ 3,850
Building	195	Wall Mounted Soap Dispenser	11	EA	\$ 150.00	\$ 1,650
Building	196	Towel and Waste Units	11	EA	\$ 250.00	\$ 2,750
Building	197	Baby Changing Station	3	EA	\$ 500.00	\$ 1,500
Building	198	Cubical Curtian Track - with Chainmail Curtian	75	LF	\$ 666.67	\$ 50,000
Building	199	Mop Racks	2	EA	\$ 200.00	\$ 400
Building	200	Whiteboard 60"x 36" Office	-	EA	\$ 300.00	\$ -
Building	201	Fire Extinguishers	6	EA	\$ 200.00	\$ 1,200
Building	202	Fire Extinguisher Cabinets	6	EA	\$ 350.00	\$ 2,100
Building	203	CG-1 Corner Guards	-	EA	\$ 100.00	\$ -
Building	204	Knox Boxes	2	EA	\$ 1,250.00	\$ 2,500
10A MISCELLANEOUS SPECIALTIES						\$ 78,600
10B SIGNAGE						
Building	205	Room ID	37	EA	\$ 250.00	\$ 9,250
Building	206	Restroom ID	5	EA	\$ 250.00	\$ 1,250
Building	207	Elevator ID	5	EA	\$ 250.00	\$ 1,250
Building	208	Stair ID	4	EA	\$ 250.00	\$ 1,000
Building	209	Exit ID	7	EA	\$ 250.00	\$ 1,750
Building	210	Office ID	4	EA	\$ 250.00	\$ 1,000
Building	211	Exterior Room ID	2	EA	\$ 250.00	\$ 500
Building	212	Project Sign	1	EA	\$ 5,000.00	\$ 5,000
10B SIGNAGE						\$ 21,000
11A EQUIPMENT						
Building	213	Fridge / Freezer - Staff Lounge	1	EA	\$ 3,000.00	\$ 3,000
11A EQUIPMENT						\$ 3,000
12A FURNISHINGS						
Building	214	Manual Roller Shade	-	EA	\$ 550.00	\$ -
Building	215	ACB-01 - Armstrong Metalworks	675	EA	\$ 683.31	\$ 461,236
Building	216	ACB-02 - Arktura - Atmospha Swell	9	EA	\$ 58.00	\$ 522
Building	217	ACP-01 - Arktura - Sound Star Module - 5' Diameter	36	EA	\$ 4,168.58	\$ 150,069
Building	218	ACP-02 - Arktura - Geo Sound Panel	61	EA	\$ 740.84	\$ 45,191
Building	219	ACP-03 - Arktura - Soft Grid Scale	9	EA	\$ 2,361.11	\$ 21,250
Building	220	ACP-04 - Arktura - Lyra Direct Applied	1,855	SF	\$ 32.56	\$ 60,399
Building	221	MCP-01 - Arktura - Vapor Cluster	995	SF	\$ 135.61	\$ 134,932
Building	222	MCP-02 - Arktura - Vapor Frequency	570	SF	\$ 250.50	\$ 142,785
Building	223	MCP-03 - Armstrong Metalworks Mesh 1 Grid	960	SF	\$ 125.00	\$ 120,000
Building	224	MP-01 - Metal Screen Hendrick Corp Flex Bar - Exterior Planetarium	678	SF	\$ 420.35	\$ 285,000
Building	225	AWP-01 - Arktura - Groove Straight - Per Finish Plan	8,100	SF	\$ 29.21	\$ 236,601
12A FURNISHINGS						\$ 1,657,985

50% Construction Documents Estimate

Project: McKinney RHHL Renovation
Date: March 28, 2025



Estimate Detail						
Area	Item	Description		Unit	Unit Cost	Amount
13A SPECIAL CONSTRUCTION						
Building	215	Cosm - Projection System - Sony GTZ 380 w/ 2 Cove Mounted Projectors	1	LS	\$ 409,200.00	\$ 409,200
Building	216	Cosm - Workstation with Premium Media Program - 5-year	1	LS	\$ 76,750.00	\$ 76,750
Building	217	Cosm - 26-Foot NanoSeam Dome	1	EA	\$ 223,330.00	\$ 223,330
Building	218	Cosm - Audio & Light System, Standard Power	1	EA	\$ 97,330.80	\$ 97,331
Building	218	Cosm - Audio & Light System, LED Cove Lights	1	EA	\$ 80,062.40	\$ 80,062
Building	219	Crossland Unforeseen Conditions	1	LS	\$ 100,000.00	\$ 100,000
13A SPECIAL CONSTRUCTION						\$ 986,673
14A CONVEYING EQUIPMENT						
Building	220	TKE EOX Traction Elevator - EXCLUDES TKE EVO200	4	STOPS	\$ 55,000.00	\$ 220,000
Building	221	Elevator Code Compliance - 2 Way Radio	1	LS	\$ 8,500.00	\$ 8,500
Building	222	Elevator Code Compliance - Stretched Compliance	1	EA	\$ 10,000.00	\$ 10,000
14A CONVEYING EQUIPMENT						\$ 238,500
21A FIRE PROTECTION						
Building	223	Sprinkler, Reworking Existing System to new Layout	33,670	SF	\$ 3.85	\$ 129,630
Building	224	Sprinkler, Above & Below Ceiling Clouds and Planetarium	6,475	SF	\$ 4.85	\$ 31,404
Building	225	New Fire Valve Cabinets	6	EA	\$ 7,500.00	\$ 45,000
Building	226	Fire Pump	-	EA	\$ 35,000.00	\$ -
15C FIRE PROTECTION						\$ 206,033
22A PLUMBING						
Building	227	Domestic Water, Sanitary Waste, Vent, Piping PVC	33,670	SF	\$ 6.00	\$ 202,020
Building	228	L-1 Lavatory with Sensor Faucet	11	EA	\$ 1,500.00	\$ 16,500
Building	229	RD-1 Roof Drain	2	EA	\$ 650.00	\$ 1,300
Building	230	OD-1 Overflow Drain	-	EA	\$ 500.00	\$ -
Building	231	FD-1 Floor Drain	11	EA	\$ 500.00	\$ 5,500
Building	232	SK-1 Breakroom Sink with Sensor Faucet	1	EA	\$ 2,500.00	\$ 2,500
Building	233	MS-1 Mop Sink 36"x24"x12"	2	EA	\$ 750.00	\$ 1,500
Building	234	WC-1 Water Closet	11	EA	\$ 3,000.00	\$ 33,000
Building	235	Elevator Sump Pump and Discharge Piping	1	EA	\$ 30,000.00	\$ 30,000
Building	236	EWC-1 Electric Water Cooler	3	EA	\$ 2,500.00	\$ 7,500
Building	237	IMB-1 Ice Maker Connection Box	1	EA	\$ 500.00	\$ 500
Building	238	HB-1 Non-Freeze Hose Bib	-	EA	\$ 850.00	\$ -
Building	239	WH-1 & WH-2 Electric Water Heater - Existing	2	EA	\$ 5,000.00	\$ 10,000
Building	240	Water Conditioner - CS-1 through CS-3 - excludes salt water conditioners	3	EA	\$ 20,000.00	\$ 60,000
Building	241	Backflow Preventer, Watts LF909	1	EA	\$ 8,000.00	\$ 8,000
22A PLUMBING						\$ 378,320
23A HVAC						
Building	242	Demo Existing Ductwork and Chiller Piping	33,271	SF	\$ 2.50	\$ 83,178
Building	243	Adjust/Relocate Existing Fan Coil Units	15	EA	\$ 4,500.00	\$ 67,500
Building	244	ETI New Fan Coil Units	19	EA	\$ 7,800.00	\$ 148,200
Building	245	Copper Piping - Chilled Water / Boiler / Condensate / Refrigerant	1,884	LF	\$ 85.00	\$ 160,140
Building	246	Aaon DOAS Units - DOAS-1 through DOAS-8	8	EA	\$ 20,000.00	\$ 160,000
Building	247	EF Exhaust Fans - 400 CFM were 75 CFM	5	EA	\$ 8,500.00	\$ 42,500
Building	248	LG Split System	5	EA	\$ 12,500.00	\$ 62,500
Building	249	Automatic Balancing Valve, Strainers, Unions	84	EA	\$ 1,200.00	\$ 100,800
Building	250	Outside Air Intake	2	EA	\$ 750.00	\$ 1,500
Building	251	Redd-I Electric Duct Heaters	8	EA	\$ 2,650.00	\$ 21,200
Building	252	Paint Grade Round Spiral Ductwork	33,670	SF	\$ 8.50	\$ 286,195
Building	253	Grilles, Registers, Diffusers (GRD's)	33,670	SF	\$ 4.50	\$ 151,515
Building	254	Building Automation System (BAS)	33,670	ALLOW	\$ 5.50	\$ 185,185
Building	255	Testing, Adjusting & Balancing & Commissioning	33,670	SF	\$ 0.80	\$ 26,936
23A HVAC						\$ 1,497,349

50% Construction Documents Estimate

Project: McKinney RHHL Renovation
Date: March 28, 2025



Estimate Detail						
Area	Item	Description		Unit	Unit Cost	Amount
26A ELECTRICAL						
Building	256	Electrical, Distribution	33,670	SF	\$ 15.50	\$ 521,885
Building	257	Electrical Demolition and Make Safe	33,670	SF	\$ 2.50	\$ 84,175
Building	258	Rework - MDP Main Distribution Panel 1200A	1	EA	\$ 75,000.00	\$ 75,000
Building	259	Panelboard LP1A - 100A	1	EA	\$ 12,500.00	\$ 12,500
Building	260	Panelboard LP2A - 100A	1	EA	\$ 12,500.00	\$ 12,500
Building	261	Surge Protective Device on MSB	1	EA	\$ 25,000.00	\$ 25,000
Building	262	Electrical Connections to Mechanical Equipment	56	EA	\$ 1,500.00	\$ 84,000
Building	263	Receptacle	33,670	SF	\$ 2.85	\$ 95,960
Building	264	Elevator Disconnect Switch - 480V / 100A/3P	2	EA	\$ 15,000.00	\$ 30,000
Building	265	Lighting - Unidentified/Not Shown	33,670	SF	\$ 1.49	\$ 50,000
Building	266	Light Fixture Package:	1	LS	\$ 621,500.00	\$ 621,500
Building	267	A - CONTINUOUS LINEAR SUSPENDED DIRECT/INDIRECT SLOTLIGHT, LENGTHS AS SHOWN ON PLAN	-			
Building	268	AE - SAME AS TYPE "A" BUT WITH EMERGENCY BATTERY PACK	-			
Building	269	B - 2x2 RECESSED LED ARCHITECTURAL WITH FROSTED WAVESTREAM LENS	-			
Building	270	B1 - 2x2 RECESSED LED ARCHITECTURAL	-			
Building	271	B1E - SAME AS TYPE "B1" BUT WITH EMERGENCY BATTERY PACK	-			
Building	272	BE - SAME AS TYPE "B" BUT WITH EMERGENCY BATTERY PACK	-			
Building	273	C - 6" RECESSED LED DOWNLIGHT MEDIUM DISTRIBUTION	-			
Building	274	CC - Acclaim Lighting (or similar) Dyna Graze HO Exterior	-			
Building	275	CE - SAME AS TYPE "C" BUT WITH EMERGENCY BATTERY PACK	-			
Building	276	DD - LINEAR RGBW GRAZER	-			
Building	277	F - DECORATIVE PENDANT	-			
Building	278	GG - CONTINUOUS LINEAR SUSPENDED DIRECT SLOTLIGHT, LENGTH AS SHOWN ON PLAN	-			
Building	279	GGE - SAME AS TYPE "GG" BUT WITH EMERGENCY BATTERY PACK	-			
Building	280	H - SUSPENDED PATTERNS OF MAGNETIC TRACK SYSTEM	-			
Building	281	H1 - AIMABLE HEAD FOR TYPE "H" ABOVE WITH FIXED BEAM	-			
Building	282	H2 - AIMABLE HEAD FOR TYPE "H" ABOVE WITH ON-FIX	-			
Building	283	J - 3" DIAMETER DECORATIVE PENDANT DIRECT/INDIRECT LIGHTING ELEMENTS	-			
Building	284	K - LINEAR RECESSED 3" SLOT WITH BLACK LENS	-			
Building	285	KE - SAME AS TYPE "K" BUT WITH EMERGENCY BATTERY PACK	-			
Building	286	KK - 2', 2" WIDE LINEAR RECESSED LED SLOTLIGHT	-			
Building	287	KK1 - 4', 2" WIDE LINEAR RECESSED LED SLOTLIGHT	-			
Building	288	KK1E - SAME AS TYPE "KK1" BUT WITH EMERGENCY BATTERY PACK	-			
Building	289	KKE - SAME AS TYPE "KK" BUT WITH EMERGENCY BATTERY PACK	-			
Building	290	L - COVE LIGHT LUMENWERX LED	-			
Building	291	M1 - SUSPENDED CURVED LINEAR FIXTURE AS SHOWN ON PLANS	-			
Building	292	M2 - SUSPENDED CURVED LINEAR FIXTURE AS SHOWN ON PLANS	-			
Building	293	N - 4', 2" WIDE LINEAR LED PENDANT DIRECT-INDIRECT	-			
Building	294	NE - SAME AS TYPE "N" BUT WITH EMERGENCY BATTERY PACK	-			
Building	295	P - HEXAGON CORNER PENDANT	-			
Building	296	P1 - 4" LED CYLINDER PENDANT LED	-			
Building	297	P1E - SAME AS TYPE "P1" BUT WITH EMERGENCY BATTERY PACK	-			
Building	298	Q - 12' LINEAR PENDANT	-			
Building	299	S - 4' LENSED STRIP, AIRCRAFT CABLE HUNG FROM STRUCTURE	-			
Building	300	SE - SAME AS TYPE "S" BUT WITH EMERGENCY BATTERY PACK	-			
Building	301	T - 3'6" DIAMETER DECORATIVE PENDANT DIRECT/INDIRECT	-			
Building	302	V1 - ARKTURA BACKLIGHTING PANEL	-			
Building	303	V2 - 2'X2' ARKTURA BACKLIGHTING PANEL	-			
Building	304	V3 - 2'X4' ARKTURA BACKLIGHTING PANEL	-			
Building	305	X1 - SINGLE FACED EXIT SIGN	-			
Building	306	X2 - DOUBLE FACED EXIT SIGN	-			
Building	307	X3 - SINGLE FACED EXIT SIGN BLACK FINISH	-			
Building	308	Y - LINEAR LED "RGBW" ALONG CURVED WALL TOE KICK AS SHOWN ON PLANS	-			
Building	309	Z - LINEAR LED "RGBW" AT TOE KICK AS SHOWN ON PLANS	-			
Building	310	Planetarium - Fixtures / Conduit COSM - UNKNOWN	1,265	SF	\$ 79.05	\$ 100,000
Building	311	Lighting Controls	33,670	SF	\$ 5.20	\$ 175,000
Building	312	Lightning Protection	33,670	SF	\$ 1.04	\$ 35,000

26A ELECTRICAL \$ 1,922,520

27A COMMUNICATIONS

Building	313	Telecom/Data - Demo Existing Cablings	33,670	SF	\$ 1.50	\$ 50,505
Building	314	Install 2-Post Equipment Racks	3	EA	\$ 12,500.00	\$ 37,500
Building	315	Install, Terminate, Test and Label - Category 6A Cables	418	EA	\$ 500.00	\$ 209,000

27A COMMUNICATIONS \$ 297,005

27B AUDIO/VISUAL

Building	316	General, Audio/Video Equipment	33,670	SF	\$ 2.50	\$ 84,175
Building	317	Display 1 - 55"	16	EA	\$ 10,000.00	\$ 160,000
Building	318	Display 2 - 65"	2	EA	\$ 12,500.00	\$ 25,000
Building	319	Display 5 - 98"	2	EA	\$ 45,000.00	\$ 90,000
Building	320	Display 7 - 163"	3	EA	\$ 120,000.00	\$ 360,000
Building	321	Display 12 - Vestibule Video Board	2	EA	\$ 55,000.00	\$ 110,000
Building	322	Youth Arched Video Wall	1	LS	\$ 490,000.00	\$ 490,000

50% Construction Documents Estimate

Project: McKinney RHHL Renovation
Date: March 28, 2025



Estimate Detail						
Area	Item	Description		Unit	Unit Cost	Amount
Building	323	Paging System	33,670	SF	\$ 4.46	\$ 150,000
						27B AUDIO/VISUAL \$ 1,469,175
28A FIRE ALARM						
Building	323	Fire Alarm	33,670	SF	\$ 1.35	\$ 45,455
						28A FIRE ALARM \$ 45,455
28B SECURITY						
Building	324	Security System	33,670	SF	\$ 1.50	\$ 50,505
Building	325	360 Degree Camera	6	EA	\$ 4,500.00	\$ 27,000
Building	326	Dual View Camera	2	EA	\$ 2,500.00	\$ 5,000
Building	327	3-Way Camera	6	EA	\$ 3,500.00	\$ 21,000
Building	328	Fixed Camera Exterior	7	EA	\$ 2,250.00	\$ 15,750
Building	329	Fixed Camera Interior	8	EA	\$ 1,500.00	\$ 12,000
						28B SECURITY \$ 131,255
28C ACCESS CONTROLS						
Building	330	Card Readers & Electrified Hardware	16	EA	\$ 3,500.00	\$ 56,000
Building	331	Door Contacts	7	EA	\$ 500.00	\$ 3,500
						28C ACCESS CONTROLS \$ 59,500